ZAMBIA SUGAR PLC
P.O. BOX 670240
ENGINEERING SPECIFICATION

PR (Contract) Nº.	CEF-NK-0991	
Department	Business Improvement	
Title	**People vehicle separation Ph 4 of 6**	
Nominee for Queries	Obe Emmanuel	
Project Manager	Obe Emmanuel	
Approved by:	Stella Mwale	

A. Project Introduction

At Nakambala – Zambia Sugar, one of the primary causes of workplace accidents has been the interaction between people and vehicles. In line with ABF safety standards, it is essential that physical barriers are installed wherever there is a significant risk of such interactions. These barriers should effectively separate pedestrians from vehicles and machinery as much as reasonably practicable. This applies especially to walkways and areas with high traffic involving mobile plant equipment and vehicles. Implementing robust people-vehicle separation measures will greatly reduce the likelihood of fatal incidents resulting from these interactions.

B. Scope of Work

The scope of work shall involve the construction of people vehicle separation (PVS) from Pentecostal Church junction to SDA T-junction and the area between the marshalling yard and Total filling station as follows.

- Excavation to reduce levels as per engineers' specification.
- Shaping and compaction of the levelled imported laterite.
- Concreting of the walkway in C25 including laying of waterproofing membrane and reinforcement mesh.
- Construction of the drainage.
- Construction of boxed culvert at road crossing.
- Installation of kerbstones and bollards at selected points.

Note: Refer to the attached BOQ.
Only 1 lot to be awarded to a contractor
Successful contractor will be subjected to contract to be shared.
Drawing to be issued to the successful contractor.

C. Instructions to Contractors

The duties of the Contractor during this phase of the project will include, but will not necessarily be restricted to, the following:

- Provide schedule of works.
- Coordinating own labour to ensure the works are carried out in accordance with contract specifications and in the best interests of the Client with minimal disruption to existing operations.
- Monitoring the progress of the works against the agreed schedule and initiating such actions as are required to achieve the target completion deadlines.
- Controlling quality and quantity of all site materials under the terms of the contract; monitoring compliance with environmental, health and safety regulations, as well as the Client's SHEQ requirements.
- Issuing interim and final certificates and approvals for payment by the Client.
- Monitoring all corrective work done by, or on behalf of, the contractors during the contract defect liability periods; and,
- Performing any other services specifically related to the project which may be agreed between the Contractor and the Client, including the supervision or execution of any specified tests, assisting with the commissioning of works and the verification of performance guarantees.
- Necessary work permits are obtained timeously, including excavation permit.
- Dedicated safety watch to be on site at all times whilst construction is underway.
- The Contractor is responsible to review each General Arrangement (GA) drawing, reviewing the position of the construction on site and identifying any potential clashes with existing installed services prior to commencing with the Installation.
- Should any changes be deemed necessary the Contractor shall agree these changes with the Engineer on site and "Green Line" the GA drawing accordingly, which shall be signed by the engineer prior to installation commencing.
- Area to be always left neat and tidy.
- All work to be always supervised.
- All workers assigned to undertake this task should ensure that the correct PPE is always used as prompted by area and activity.
- Contractor to provide all material for any re-work due to poor workmanship (always consult at any critical stage).
- Clear off all debris and dispose of it to the designated dump site.

D. Material / Equipment to be supplied by Zambia Sugar PLC during construction:

- Contractor to supply own material / equipment.

E. Materials to be supplied by Contractor:

- Setting out equipment
- Excavation equipment
- Hand tools and equipment
- Storage facilities for their Tools/Equipment on site

F. Construction programme

The Contractor shall submit his proposed programme of the works in sufficient detail to prove that he can comply with the Time for Completion.

The Contractor's program shall clearly indicate the completion date offered and shall make reasonable allowance for delays in obtaining materials from suppliers, delays due to inclement weather and delays which may be expected for any other reason which can be reasonably foreseen.

The Contractor will indicate in the program, how long lead time he requires for procurement of materials (if applicable) from award of Contract to site establishment.

G. Other Important notes:

- All Zambian registered companies are advised of the Bank of Zambia Act No 43 of 1966 that requires that the quotation be made in the Zambian unit of Currency, the Kwacha.
- Contractor to note that the contract value shall remain fixed during the duration of the contract.
- Contractor to note that tender maybe disqualified due to erasures and alterations.
- If any rework is done due to poor workmanship, the contractor will undertake this at his/her own cost. Including replacement of materials, if required.
- Invoicing shall only be done after successfully commissioning the system and completion certificates signed off.

H. Pricing

- All BOQs to be priced.

Note. **Award will be as per approved number of ponds**.

I. Key Dates

#	**Project Task**	**Target Dates**
1	Tender floated by	10th October 2025
2	Site Visit by	15th October 2025
3	Purchase Order placed	07th November 2025
4	Access to Site	15th November 2025

J. Documents attached to this Scope.

Title of Document	**Document Number**	**Revision**

Walkway drawing Layout		
Drainage drawing layout		

K. BOQ

Unabridged BOQ attached as **Appendix A, (TO BE COMPLETED)**

L. Zambia Sugar Responsibilities

For safe access to the site, all Illovo site safety procedures must be followed with respect to the following:

- Issuing of PO to the contractor
- Approval of HSE File
- Approval of Method Statement, Risk Assessment and QCP
- Permit to Work

M. Typical Contractor and Client Scope of Supply

- Applicable to work done at Zambia Sugar Premises.
- In the event of load shedding, the Contractor must supply their own back up generator

N. Quality Assurance Hold Points

- High level QCP approval before fabrication

O. Safety

Apart from the general safety requirements already mentioned in ZAMBIA SUGAR contracts, the following specialized safety training is required:

- None

P. Risk Responsibility

RISK	RESPONSIBLE PARTY
Delivery of materials to site	Contractor (within Contractor's scope)
Load shedding	Contractor
Mobile crane availability	Zambia Sugar
Project Overrun	Contractor
Poor workmanship / quality	Contractor

Q. Declaration by Contractor:

The Contractor will acknowledge that the contract will be withdrawn immediately, if Z.S finds the Contractor recruiting inside the Factory premises.

The rates inserted by the Tenderers will be deemed to include all requirements in these notes Labour, Materials and other free issue items, workmanship, Machinery and all ancillaries for completion of the contract.

By the submission of the Tender. Tenderers will be deemed to have fully acquainted themselves with the Tender document and to have thoroughly investigated the site and conditions, access to the local requirements and laws, supply of materials, matters affecting manufacture, delivery and storage and all aspects of construction, envisaged in the document prior to pricing and submission of their tender.

I/We have made myself / ourselves fully conversant with work to be done, have studied the tender document comprising (inter alia):

- Relevant Specifications.
- Zambia Sugar SHE Specifications
- Zambia Sugar Safety Rules and Regulations for Contractors.
- Any other Special Safety Requirements.

And understand that this tender, if accepted by us, will be deemed as a contract under the standard trading conditions of Zambia Sugar for the due completion of the work in the time and for the sum specified.

Contractor's signature…… Signature of witness……

Designation CEO…… Designation Projects Manager……

Date 21st October 2025…… Date 21st October 2025……

Company address and stamp House no. 103, Zwilipili Road, Kafue Town, Kafue.……

DEMAS ENGINEERING SERVICES LIMITED
21 OCT 2025
PLOT 200 NAMULONGA, MAZABUKA